

**CONTRACT SPECIAL PROVISIONS
For
HAYMARKET TOWN PARK STREETScape IMPROVEMENTS PROJECT**

Item CONTRACT SPECIAL PROVISIONS

CSP-1 SHOP AND WORK DRAWINGS 2
CSP-2 AS-BUILT DRAWINGS AND SPECIFICATIONS 2
CSP-3 TEMPORARY SEEDING 2
CSP-4 PIPE BEDDING MATERIAL 2
CSP-5 CONNECTION TO EXISTING DRAINAGE STRUCTURES 3
CSP-6 ERADICATION OF PAVEMENT MARKINGS..... 3

CONTRACT SPECIAL PROVISIONS
For
HAYMARKET TOWN PARK STREETSCAPE IMPROVEMENTS PROJECT

CSP-1 SHOP AND WORK DRAWINGS

All shop drawings, working drawings, detail sheets, materials and sample submittals required by Contract are to be indicated on the Construction Schedule shall include at least 30 day review, approval or correction period including re-submittals time, where required, so that there is no delay to the work. All submittals are to be made, in the form and the number specified in the Specifications, to the Construction Engineer who will be responsible for logging, checking, transmitting to the relevant approving entity, expediting and returning to Contractor for action all reviewed submittals. Although the Town will cooperate in making a timely review of the submittals, the Town cannot be held responsible for any delay in the review.

CSP-2 AS-BUILT DRAWINGS AND SPECIFICATIONS

The Contractor shall maintain at the Field Office a complete set of full-size plans and specifications. During the Contract the Contractor shall mark-up these plans and specifications concurrent with changes in the work in order to maintain an as-built record of the work. The Engineer will review these as-built plans and specifications monthly to verify that they are being kept current. On completion of the Project, and as a requirement for final payment, the Contractor shall deliver the original set and one copy of the as-built drawings to the Construction Engineer. **The Contractor shall also provide as-built plans in electronic format (as PDF files) to the Construction Engineer.** With the as-built drawings and specifications, the Contractor will submit a certification signed by an officer of the company that all work has been completed in accordance with the Plans and Specifications with the exception of the changes noted on the as-built plans and specifications.

CSP-3 TEMPORARY SEEDING

Temporary seeding shall be placed in accordance with the Virginia Erosion and Sediment Control Handbook and as directed by the Engineer to reduce erosion and sedimentation in disturbed areas. Payment for furnishing and placing temporary seed shall be included in the Contract Unit Price for other Bid Items.

CSP-4 PIPE BEDDING MATERIAL

The cost of furnishing and installing pipe bedding material and backfill material as required by VDOT standards and specifications and geotechnical recommendations shall be included in the Contract Unit Price for the respective pipe. Where pipe is installed underneath pavement, regular backfill material in accordance with Section 302 of the Road and Bridge Specifications shall extend

to pavement subbase. The cost of this backfill shall be included in the Contract Unit Price for the respective pipe.

CSP-5 CONNECTION TO EXISTING DRAINAGE STRUCTURES

Where plans call for proposed storm sewer to tie into an existing drainage structure, the Contractor shall determine what will be required to make proper connection to the existing structure. Costs associated with structure modifications shall not be paid for as a separate item, but shall be included in the price for other storm drainage items.

CSP-6 ERADICATION OF PAVEMENT MARKINGS

Eradication of all existing pavement markings, which are in conflict with Contract plan markings, will not be paid for at a separate Contract Unit Price. The cost of such eradication shall be included in the costs bid for pavement line markings.